



## FY25 ROADWAY IMPROVEMENT PROJECT – ADDENDUM I

11.6.2024

This addendum updates the above referenced project.

1. Paving around the columns around the skywalk may be sawcut around them.
2. Model number or brand for the 2' metal curb w/vane openings Modified to 2 – metal curb openings at each location, Neenah R-3262-4 or approved equal.
3. Paint striping to be regular paint.
4. Limits of construction Contractor to take measures to limit disturbance to 12" beyond back of curb where adjacent to existing trees.
5. Permitting responsibility of contractor.
  - a. City of Stillwater Right of Way permitting the only required permit.
  - b. Submit Notice of Intent to ODEQ
6. Gates to match existing
7. Computer at Entrance 1 to be removed. Curb cut to be eliminated.
8. Pedestal for gate entry can remain or new one installed. Powder coat to match existing campus standards.
9. Fill soil to be nutrient rich screened sandy loam that is free of rocks, roots and other materials.
10. Preference for hand poured curb.
11. Preference for bored over trenched
12. Grounds crew to coordinate with contractor installation of sleeves for irrigation expansion. Sleeves at the cost of MTC.

### Plan Changes

1. Sheet C1.0 updated revision log
2. Sheet C4.0 updated limits of removal of storm pipe. Grate inlets to remain.
3. Sheets C5.0 and C6.0. Grate inlets with hoods to remain. Add 8" HDPE storm pipe to tie in drain to existing SDMH.
4. Sheets C7.1 and C7.2 relocated electric conduit to north side of trees.
5. Sheets C7.1 and C7.4 modified 2' Metal Curb Openings to 2 – 16" metal curb openings Neenah R-3262-4 or approved equal.

Additional questions should be sent to [jeremyz@meridiantech.edu](mailto:jeremyz@meridiantech.edu)